



# ULV-150

3 x 3 - 7A

## 150GPM UL Fire Pump System






## NFPA-20 Submittal Packet

## NFPA-20 Fire Pump

3-383-7A

## ULV-150

Compact Residential Package  
Design Condition: 150GPM @ 60PSI



### System Components per NFPA-20

#### System Specifications:

- Motor
- 10 Horsepower Electric
- 230 Volt, 46 Amp
- Single Phase
- 3450 RPM

#### Pump

- UL Vertical Inline Fire Pump
- 3" Suction (Grooved)
- 3" Discharge (Grooved)
- 3" Test Connection (Grooved)
- 175 PSI max working pressure

#### System Components (UL Listed by Manufacturer)

- 1- Limited Service Fire Pump Controller
- 2- Electric Motor (UL Recognized)
- 3- Discharge Butterfly Valve (Monitored)
- 4- Test Connection Butterfly Valve (Monitored)
- 5- Case Relief Valve
- 6- Check Valve
- 7- Vertical Inline Fire Pump
- 8- Suction OS&Y (Monitored)

#### Dimensions

- 36" Depth
- 68" Height
- 34" Width

\*All dimensions are approximate and subject to change without notice.




## NFPA-20 Fire Pump

3-383-7A

with Jockey Pump

# ULV-150

Compact Residential Package  
Design Condition: 150GPM @ 60PSI



### System Components per NFPA-20

#### System Specifications:

- Motor
- 10 Horsepower Electric
- 230 Volt, 46 Amp
- Single Phase
- 3450 RPM

#### Pump

- UL Vertical Inline Fire Pump
- 3" Suction (Grooved)
- 3" Discharge (Grooved)
- 3" Test Connection (Grooved)
- 175 PSI max working pressure

#### System Components (UL Listed by Manufacturer)

- 1- Limited Service Fire Pump Controller
- 2- Electric Motor (UL Recognized)
- 3- Discharge Butterfly Valve (Monitored)
- 4- Test Connection Butterfly Valve (Monitored)
- 5- Case Relief Valve
- 6- Check Valve
- 7- Vertical Inline Fire Pump
- 8- Suction OS&Y (Monitored)

#### Dimensions

- 36" Depth
- 68" Height
- 39" Width

\*All dimensions are approximate and subject to change without notice.

# 900 Series Single Stage Inline Fire Pumps



MODEL 383



Built Per  
N.F.P.A. 20

**ap AURORA®**

**PENTAIR PUMP GROUP**

# Aurora 383 Series Pumps

VERTICAL Inline Close Coupled Fire Pumps are specifically designed for vertical mounting. The suction and discharge nozzles are located on the same centerline 180° apart. Vertical pumps significantly reduce required mounting space. They are easy to maintain. Simply remove eight capscrews and the motor and bracket assembly is easily removed from the casing without disturbing the piping. The impeller is direct coupled to the motor shaft for easy maintenance, to minimize impeller run out and to reduce noise.

The inline casing is heavily ribbed to resist pipe strain and is provided with a support to simplify mounting to a base or foundation. Packing is provided when suction pressure is greater than 30 PSIG; packing with lantern ring and flush line is furnished for suction pressures of 30 PSIG or less. Look through this bulletin for additional details & specifications.

Back pull-out inline case design simplifies disassembly. The suction and discharge piping or alignment is not disturbed as the casing remains in the pipeline. Simply remove the motor and bracket assembly for service or inspection.

Computer machined major components with 360° registered fits assure parts concentricity.

**Note:** Front case wearing rings are standard on all size pumps. Rear case rings are standard on all sizes except the 2x2x9C. The 2x2x9C does not require a wear ring.

## STANDARD


Bronze fitted pump construction  
Bronze shaft sleeve  
Split bronze packing gland  
Carbon steel shaft  
125# ANSI flange drilling  
Dynamically balanced vacuum cast impeller  
Stainless Steel impeller screw & washer  
Bronze case wearing ring(s)  
Graphite impregnated acrylic packing  
Motor:  
NEMA-HI JP  
Factory performance tested in accordance with NFPA-20

## ACCESSORIES

Suction and discharge pressure gauges  
Air release valve  
Circulation relief valve  
Hose valve header  
Hose valves  
Flow meter  
Jockey pump  
Optional flange drillings  
125 lb suction - 250 lb discharge  
250 lb suction and discharge

- |                                                                                                                                                                                                       |                                                                                                         |                                                                                                                                                                                                                                                                               |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1 BACK PULL-OUT CASING with inline suction and discharge.                                                                                                                                             | design provides high efficiency and low wear for long service life.                                     | 9 BRONZE SHAFT SLEEVE extends full length of stuffing box to protect motor shaft. The shaft sleeve is slip fit over the shaft and then is keylocked. Shaft sleeve and impeller screw are sealed by "O"-ring gaskets to eliminate corrosion of the shaft by the pumped liquid. |
| 2 CASE WEARING RING prevents wear on casing and is easily and inexpensively replaced.                                                                                                                 | 5 CARBON STEEL SHAFT is designed for minimum deflection at maximum load.                                | 10 STANDARD MOTOR approved for 383 Series pump service by NEMA and the HYDRAULIC INSTITUTE provides low noise level pump operation.                                                                                                                                           |
| 3 SUPPORT simplifies mounting. The pump can be fastened to the floor, a base or foundation.                                                                                                           | 6 TWO PIECE BRONZE PACKING GLAND provides easy packing maintenance.                                     | 11 VOLUTE TYPE SUCTION inlet pre-rotates suction liquid.                                                                                                                                                                                                                      |
| 4 DYNAMICALLY BALANCED IMPELLER is keyed to the shaft and secured by a capscrew and washer. Vacuum casting and quality controlled manufacturing process assures consistent high performance. Enclosed | 7 FACTORY PERFORMANCE TEST guarantees performance at specified pump operating conditions.               |                                                                                                                                                                                                                                                                               |
|                                                                                                                                                                                                       | 8 FLUSH LINE with valve (when used) from discharge provides easy water seal adjustment to lantern ring. |                                                                                                                                                                                                                                                                               |

## Vertical Fire Pump Features






Customer : TALCO INDUSTRIES, INC.  
Project name : 150 @ 60

# Pump Performance Curve

Encompass 3.0 - 24.3.4




|                                      |                       |                                  |                   |
|--------------------------------------|-----------------------|----------------------------------|-------------------|
| Item Number / Tags                   | : 001                 | Size                             | : 3-383-7A        |
| Service                              | :                     | Stages                           | : 1               |
| Quantity                             | : 1                   | Driver type                      | : Motor           |
| Quote number                         | : 243627              | Frequency                        | : 60 Hz           |
| Date last saved                      | : 30 Oct 2024 4:48 PM | Speed, rated                     | : 3500 rpm        |
| Flow, rated                          | : 150.0 USgpm         | Based on curve number            | : 383-3X3X7A-3500 |
| Differential head / pressure, rated  | : 60.00 psi           | Efficiency                       | : 58.68 %         |
| Flange rating (suction / discharge)  | : 125/125             | Max working pressure, allowable  | : 175.0 psi.g     |
| Secondary Point (150% of rated flow) | : 225.0 USgpm         | Max Shutoff Head (Calculated)    | : 67.00 psi       |
| Secondary Point (65% of rated head)  | : 39.00 psi           | Max suction pressure, allowable  | : 108.0 psi.g     |
| Max Shutoff per NFPA                 | : 84.00 psi           | Pump shutoff w/ suction pressure | : 77.00 psi.g     |
|                                      |                       | Power driver, minimum            | : 10.00 hp        |

## General Arrangement

### WARNING

DO NOT OPERATE THIS MACHINE WITHOUT PROTECTIVE GUARD IN PLACE. ANY OPERATION OF THIS MACHINE WITHOUT PROTECTIVE GUARD CAN RESULT IN SEVERE BODILY INJURY.



| X    | YY   | BW   | VD    | DF   | DC   |
|------|------|------|-------|------|------|
| 9.50 | 9.50 | 4.50 | 10.25 | 8.81 | 5.19 |

| DE   | AG    | P     | AB   | CP    | Base Flange Size |
|------|-------|-------|------|-------|------------------|
| 6.13 | 17.00 | 12.25 | 7.63 | 36.00 | 3.00             |

#### NOTES:

**Not for construction, installation, or application purposes unless certified.**

All dimensions are in inches

Dimensions may vary  $\pm .38$ " (10mm) due to normal manufacturing tolerances.

See configuration for estimated total weight.

| Pump Data         |                     |
|-------------------|---------------------|
| Series            | Inline              |
| Model             | 3-383-7A            |
| Size              | 3x3x7A              |
| Flow              | 150.0 USgpm         |
| Rated Pressure    | 60.00 psi.g         |
| RPM               | 3500 rpm            |
| Rotation          | Right handed        |
| Liquid Type       | Water               |
| Discharge Size    | 3.00 in             |
| Suction Size      | 3.00 in             |
| Impeller Diameter | 6.19 in             |
| Connection Type   | 125/125             |
| Base Type         | Pipe flange support |
| -                 | -                   |

| Pump Materials of Construction |                                     |
|--------------------------------|-------------------------------------|
| Pump                           | Bronze fitted with Cast Iron casing |
| Shaft                          | Carbon Steel                        |
| Motor Data                     |                                     |
| Power                          | 10.00 hp                            |
| Phase                          | 1                                   |
| Frequency                      | 60 Hz                               |
| Volts                          | 230 V                               |
| RPM                            | 3600                                |
| Frame                          | 215JP                               |
| Service Factor                 | 1.15                                |
| Enclosure                      | ODP                                 |
| Manufacturer                   | Weg                                 |

| Site Information |             |
|------------------|-------------|
| Elevation        | 300.0 ft    |
| Temperature      | 77.00 deg F |

| Estimated Weights |          |
|-------------------|----------|
| Pump              | 153.0 lb |
| Driver            | 0.00 lb  |

| Quote Information |                        |             |  |
|-------------------|------------------------|-------------|--|
| Customer          | TALCO INDUSTRIES, INC. |             |  |
| Customer Quote    | 0                      |             |  |
| Job Name          | Default                |             |  |
| Market            | -                      |             |  |
|                   | Quote Item             | 001         |  |
|                   | Quote Date             | 10 Oct 2023 |  |



# Fire Pump Controller



# TORNATECH

Project: \_\_\_\_\_

Customer: \_\_\_\_\_

Engineer: \_\_\_\_\_

Pump Manufacturer: \_\_\_\_\_

## Technical Data Submittal Document



# Model GPL

Limited Service Full Voltage  
Across the Line Start  
Electric Fire Pump Controller

### Contents:

Data Sheets  
Dimensional Data  
Wiring Schematics  
Field Connections

Note: The drawings included in this package are for controllers covered under our standard offering. Actual AS BUILT drawings may differ from what is shown in this package.




N.Y.C.  
APPROVED



May 2024



From normal incoming power through Disconnecting Means (IS/CB)\*



N.Y.C.  
APPROVED



|                                                         |                                                                                                                                                                                                                                                                                                                  |                                                                                              |
|---------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|
| <b>Standard, Listings, Approvals and Certifications</b> | Built to NFPA 20 (latest edition)                                                                                                                                                                                                                                                                                |                                                                                              |
|                                                         | Underwriters Laboratory (UL)                                                                                                                                                                                                                                                                                     | • UL218 - Fire Pump Controllers                                                              |
|                                                         | New York City                                                                                                                                                                                                                                                                                                    | Accepted for use in the City of New York by the Department of Buildings                      |
|                                                         | <b>Optional</b>                                                                                                                                                                                                                                                                                                  |                                                                                              |
|                                                         | CE Mark                                                                                                                                                                                                                                                                                                          | Various EN, IEC & CEE directives and standards                                               |
| <b>Enclosure</b>                                        | <b>Protection Rating</b><br>Standard: NEMA 2<br><b>Optional</b><br>NEMA 12                      NEMA 4X-304 sst painted<br>NEMA 3                        NEMA 4X-304 sst brushed finish<br>NEMA 3R                      NEMA 4X-316 sst painted<br>NEMA 4                         NEMA 4X-316 sst brushed finish |                                                                                              |
|                                                         | <b>Accessories</b><br>• Bottom entry gland plate<br>• Lifting Lugs<br>• Keylock handle                                                                                                                                                                                                                           | <b>Paint Specifications</b><br>• Red RAL3002<br>• Powder coating<br>• Glossy textured finish |
|                                                         |                                                                                                                                                                                                                                                                                                                  |                                                                                              |

|                                      |                           |
|--------------------------------------|---------------------------|
| <b>Shortcircuit Withstand Rating</b> | 120V to 240V - 1ph - 60Hz |
| Standard                             | 100,000A                  |



|                                    |                                                                                                                                                                                                                                                                                                                                                                                           |
|------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Limitations</b>                 | <ul style="list-style-type: none"><li>• Across the line starting only</li><li>• Horsepower rating of maximum 30hp</li><li>• Can only be installed where acceptable by the authority having jurisdiction</li><li>• Not accepted in FM insured property</li></ul>                                                                                                                           |
| <b>Ambient Temperature Rating</b>  | <b>Standard:</b><br>4°C to 40°C / 39°F to 104°F<br><b>Optional:</b><br>4°C to 55°C / 39°F to 131°F<br>Controllers built in Dubai, UAE (Tornatech FZE) are supplied standard with 55°C rating.                                                                                                                                                                                             |
| <b>Surge Suppression</b>           | Surge arrestor rated to suppress surges above line voltage                                                                                                                                                                                                                                                                                                                                |
| <b>Disconnecting Means</b>         | <ul style="list-style-type: none"><li>• Door interlocked in the ON position</li><li>• Circuit breaker continuous rating not less than 115% of motor full load current</li><li>• Overcurrent sensing non-thermal type, magnetic only</li><li>• Instantaneous trip setting of not more than 20 times the motor full load current</li><li>• Common flange mounted operating handle</li></ul> |
| <b>Service Entrance Rating</b>     | Suitable as service entrance equipment                                                                                                                                                                                                                                                                                                                                                    |
| <b>Emergency Start Handle</b>      | <ul style="list-style-type: none"><li>• Flange mounted</li><li>• Integrated limit switch</li><li>• Pull and latch activation</li><li>• Across the line start (direct on line)</li></ul>                                                                                                                                                                                                   |
| <b>Locked Rotor Protector</b>      | <ul style="list-style-type: none"><li>• Operate shunt trip to open circuit breaker</li><li>• Trip between 8 and 20 seconds</li><li>• Factory set at 600% of motor full load current</li></ul>                                                                                                                                                                                             |
| <b>Electrical Readings</b>         | <ul style="list-style-type: none"><li>• Voltage phase to phase (normal power)</li><li>• Amperage of each phase when motor is running</li></ul>                                                                                                                                                                                                                                            |
| <b>Pressure Readings</b>           | <ul style="list-style-type: none"><li>• Continuous system pressure display</li><li>• Cut-in and Cut-out pressure settings</li></ul>                                                                                                                                                                                                                                                       |
| <b>Pressure and Event recorder</b> | <ul style="list-style-type: none"><li>• Pressure readings with date stamp</li><li>• Event recording with date stamp</li><li>• Under regular maintained operation, events are stored in memory for the life of the controller.</li><li>• Data viewable on operator interface display screen</li><li>• Downloadable by USB port to external memory device</li></ul>                         |
| <b>Pressure Sensing</b>            | <ul style="list-style-type: none"><li>• Pressure transducer and run test solenoid valve assembly for fresh water application</li><li>• Pressure sensing line connection 1/2" Female NPT</li><li>• Drain connection 3/8"</li><li>• Rated for 0-500PSI working pressure (standard display at 0-300PSI)</li><li>• Externally mounted with protective cover</li></ul>                         |



|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                    |                                                                                                                                                   |
|------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Audible Alarm</b>               | Alarm buzzer - 85dB at 3 meters                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                                                                                                                                    |                                                                                                                                                   |
| <b>Visual Indications</b>          | <ul style="list-style-type: none"> <li>• Power available</li> <li>• Motor run</li> <li>• Periodic test</li> <li>• Manual start</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <ul style="list-style-type: none"> <li>• Deluge valve start</li> <li>• Remote automatic start</li> <li>• Remote manual start</li> <li>• Emergency start</li> </ul> | <ul style="list-style-type: none"> <li>• Pump on demand/Automatic start</li> <li>• Pump room temperature (°F or °C)</li> <li>• Lockout</li> </ul> |
| <b>Visual &amp; Audible Alarms</b> | <p>Visual</p> <ul style="list-style-type: none"> <li>• Control voltage not healthy</li> <li>• Invalid cut-in</li> <li>• Lock rotor current</li> <li>• Loss of power</li> <li>• Low ambient temperature</li> <li>• Low water level</li> <li>• Motor trouble</li> <li>• Phase reversal (normal power)</li> </ul> <p>Visual and audible</p> <ul style="list-style-type: none"> <li>• Fail to start</li> </ul> <p>Overcurrent</p> <ul style="list-style-type: none"> <li>• Overcurrent</li> <li>• Overvoltage</li> <li>• Phase loss L1</li> <li>• Phase loss L2</li> <li>• Phase loss L3</li> <li>• Phase unbalanced</li> <li>• Pressure transducer fault detected</li> </ul> <p>Pump on demand</p> <ul style="list-style-type: none"> <li>• Pump on demand</li> <li>• Pump room alarm</li> <li>• Service required</li> <li>• Undercurrent</li> <li>• Undervoltage</li> <li>• Check weekly test solenoid</li> <li>• Weekly test cut-in reached</li> </ul> |                                                                                                                                                                    |                                                                                                                                                   |
| <b>Remote Alarm Contacts</b>       | <p>DPDT-8A-250V.AC</p> <ul style="list-style-type: none"> <li>• Power available</li> <li>• Phase reversal</li> <li>• Motor run</li> <li>• Common pump room alarm (field re-assignable)** <ul style="list-style-type: none"> <li>• Overvoltage</li> <li>• Undervoltage</li> <li>• Phase unbalance</li> <li>• Low pump room temperature</li> <li>• High Pump room temperature</li> </ul> </li> <li>• Common motor trouble (field re-assignable)** <ul style="list-style-type: none"> <li>• Overcurrent</li> <li>• Fail to start</li> <li>• Undercurrent</li> <li>• Ground fault</li> </ul> </li> <li>• Free (field programmable)**</li> </ul>                                                                                                                                                                                                                                                                                                           |                                                                                                                                                                    |                                                                                                                                                   |

\*\*Tornatech reserves the right to use any of these three alarm points for special specific application requirements.



|                                                  |                                                                                                                                                                                                                 |                                                                                                                                                               |                                                                                                                                                                  |
|--------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>ViZiTouch V2.1<br/>Operator Interface</b>     | <ul style="list-style-type: none"> <li>• Embedded microcomputer with software PLC logic</li> <li>• 7.0" color touch screen (HMI technology)</li> <li>• Upgradable software</li> <li>• Multi-language</li> </ul> |                                                                                                                                                               |                                                                                                                                                                  |
| <b>Communication<br/>Protocol<br/>Capability</b> | <ul style="list-style-type: none"> <li>• Protocol: Modbus</li> <li>• Connection type: Shielded female connector RJ45</li> <li>• Frame Format: TCP/IP</li> <li>• Addresses: See bulletin MOD-GPx</li> </ul>      |                                                                                                                                                               |                                                                                                                                                                  |
| <b>Operation</b>                                 | <b>Automatic Start</b>                                                                                                                                                                                          | <ul style="list-style-type: none"> <li>• Start on pressure drop</li> <li>• Remote start signal from automatic device</li> <li>• Deluge valve start</li> </ul> |                                                                                                                                                                  |
|                                                  | <b>Manual Start</b>                                                                                                                                                                                             | <ul style="list-style-type: none"> <li>• Start pushbutton</li> <li>• Run test pushbutton</li> <li>• Remote start from manual device</li> </ul>                |                                                                                                                                                                  |
|                                                  | <b>Stopping</b>                                                                                                                                                                                                 | <ul style="list-style-type: none"> <li>• Manual with Stop pushbutton</li> <li>• Automatic after expiration of minimum run timer ***</li> </ul>                |                                                                                                                                                                  |
|                                                  | <b>Timers</b>                                                                                                                                                                                                   | Field Adjustable & Visual Countdown                                                                                                                           | <ul style="list-style-type: none"> <li>• Minimum run timer ***(off delay)</li> <li>• Sequential start timer (on delay)</li> <li>• Periodic test timer</li> </ul> |
|                                                  | <b>Actuation</b>                                                                                                                                                                                                | Visual Indication                                                                                                                                             | <ul style="list-style-type: none"> <li>• Pressure</li> <li>• Non-pressure</li> </ul>                                                                             |
|                                                  | <b>Mode</b>                                                                                                                                                                                                     |                                                                                                                                                               | <ul style="list-style-type: none"> <li>• Automatic</li> <li>• Non-automatic</li> </ul>                                                                           |

\*\*\*Can only be used if approved by the AHJ



|      |                                                                                                                                                                                                                                    |
|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| A4   | Flow switch provision                                                                                                                                                                                                              |
| A8   | Foam pump application w/o pressure transducer and run test solenoid valve.                                                                                                                                                         |
| A9   | Low zone pump control function                                                                                                                                                                                                     |
| A10  | Middle zone pump control function                                                                                                                                                                                                  |
| A11  | High zone pump control function                                                                                                                                                                                                    |
| A13  | Non-pressure actuated controller w/o pressure transducer and run test solenoid valve                                                                                                                                               |
| A16  | Lockout/interlock circuit from equipment installed inside the pump room                                                                                                                                                            |
| B11  | Built in alarm panel (120V.AC supervisory power) providing indication for:<br>• Audible alarm & silence pushbutton for motor run, phase reversal, loss of phase.<br>• Pilot lights for loss of phase & supervisory power available |
| B11B | Built in alarm panel same as B11 but 220-240VAC supervisory power                                                                                                                                                                  |
| B19A | High motor temperature c/w thermostat relay and alarm contacts (DPDT)                                                                                                                                                              |
| B19B | High motor temperature c/w PT100 relay and alarm contacts (DPDT)                                                                                                                                                                   |
| B21  | Ground fault alarm detection c/w visual indication and alarm contact (DPDT)                                                                                                                                                        |
| C1   | Extra motor run alarm contact (DPDT)                                                                                                                                                                                               |
| C4   | Periodic test alarm contact (DPDT)                                                                                                                                                                                                 |
| C6   | Low discharge pressure alarm contact (DPDT)                                                                                                                                                                                        |
| C7   | Low pump room temperature alarm contact (DPDT)                                                                                                                                                                                     |
| C10  | Low water reservoir level alarm contact (DPDT)                                                                                                                                                                                     |
| C11  | High electric motor temperature alarm contact (DPDT)                                                                                                                                                                               |
| C12  | High electric motor vibration c/w visual indication and alarm contact (DPDT)                                                                                                                                                       |
| C14  | Pump on demand / automatic start alarm contact (DPDT)                                                                                                                                                                              |
| C15  | Pump fail to start alarm contact (DPDT)                                                                                                                                                                                            |
| C16  | Control voltage healthy alarm contact (DPDT)                                                                                                                                                                                       |
| C17  | Flow meter valve loop open c/w visual indication and alarm contact (DPDT)                                                                                                                                                          |
| C18  | High water reservoir level c/w visual indication and alarm contact (DPDT)                                                                                                                                                          |

|      |                                                                                                            |
|------|------------------------------------------------------------------------------------------------------------|
| C19  | Emergency start alarm contact (DPDT)                                                                       |
| C20  | Manual start alarm contact (DPDT)                                                                          |
| C21  | Deluge valve start alarm contact (DPDT)                                                                    |
| C22  | Remote automatic start alarm contact (DPDT)                                                                |
| C23  | Remote manual start alarm contact (DPDT)                                                                   |
| C24  | High pump room temperature alarm contact (DPDT)                                                            |
| C25  | Second set of standard alarm contacts (DPDT) (Typical for city of Los Angeles and Denver)                  |
| Cx   | Additional visual and alarm contact (Specify function) (DPDT)                                              |
| D1   | Low suction pressure transducer for fresh water rated at 0-300PSI with visual indication and alarm contact |
| D1A  | Low suction pressure transducer for sea water rated at 0-300PSI with visual indication and alarm contact   |
| D13A | High withstand rating for<br>• 380V to 480V = 65kA*<br>• 600V = 25kA*                                      |
| D14  | Anti-condensation heater & thermostat                                                                      |
| D14A | Anti-condensation heater & humidistat                                                                      |
| D14B | Anti-condensation heater & thermostat & humidistat                                                         |
| D15  | Tropicalization                                                                                            |
| D18  | CE Mark with factory certificate                                                                           |
| D26  | Modbus with RTU frame format and RS485 connection                                                          |
| D27  | Motor heater connection (external single phase power source and heater on/off contact)                     |
| D27A | Motor heater connection (internal single phase power source and heater on/off contact)                     |
| D28  | Customized drawing set                                                                                     |
| D34A | Field programmable I/O board - 5 Input / 5 output                                                          |
| D36  | Redundant pressure transducer for fresh water rated for 0-500PSI                                           |
| D36A | Redundant pressure transducer for sea water rated for 0-500PSI                                             |

Note: Options chosen from this page are not electrically represented on the wiring schematics in this submittal package.



|     |                                        |
|-----|----------------------------------------|
| L01 | Other language and English (bilingual) |
| L02 | French                                 |
| L03 | Spanish                                |
| L04 | German                                 |
| L05 | Italian                                |
| L06 | Polish                                 |
| L07 | Romanian                               |
| L08 | Hungarian                              |
| L09 | Slovakian                              |
| L10 | Croatian                               |
| L11 | Czech                                  |
| L12 | Portuguese                             |
| L13 | Dutch                                  |
| L15 | Turkish                                |
| L16 | Swedish                                |
| L21 | Danish                                 |
| L25 | Chinese                                |
| L28 | Finnish                                |
| L29 | Norwegian                              |

Additional Options:

---

---


---

---

---

Note: Options chosen from this page are not electrically represented on the wiring schematics in this submittal package.

### ViZiTouch V2.1 Operator Interface



- |                        |                          |
|------------------------|--------------------------|
| 1 - Color touch screen | 3 - Power LED (3 colors) |
| 2 - Onscreen menu      | 4 - START button         |
| • HOME page            | 5 - STOP button          |
| • ALARM page           | 6 - Not Used             |
| • CONFIGURATION page   | 7 - RUN TEST button      |
| • HISTORY page         | 8 - Alarm buzzer         |
| • SERVICE page         |                          |
| • MANUAL page          |                          |
| • LANGUAGES page       |                          |

**TORNATECH**© Tornatech, Inc. Not for construction.  
Subject to change without notice.



BY DD/MM/YY

DRAWN BY ACD 28/02/23


FINAL APPROVAL FC 28/02/23

**LIMITED SERVICE PUMP CONTROLLER****MODEL: GPL**

BUILT TO THE LATEST EDITION OF THE NFPA20 &amp; NFPA70

THIRD ANGLE  
PROJECTIONDRAWING NUMBER  
**GPL-DI800/E**  
DWG REV. 0  
SHEET 1 OF 1

Sensing Line Connection - 1/2" F.NPT

**Voltage / Power Table**

| Voltage         | Min HP | Max HP |
|-----------------|--------|--------|
| <b>1 Phase</b>  |        |        |
| 110 - 120       | 1      | 7.5    |
| 208             | 3      | 15     |
| 220 - 240       | 3      | 15     |
| <b>3 Phases</b> |        |        |
| 208             | 3      | 30     |
| 220 - 240       | 3      | 30     |
| 380 - 400 - 415 | 3      | 30     |
| 440 - 480       | 3      | 30     |
| 600             | 3      | 30     |

**Notes:**

- Standard NEMA: NEMA 2
- Standard paint : textured red RAL 3002.
- All dimensions are in inches [millimeters].
- Center of screen: 29-5/8" [751] from bottom (no feet).
- Bottom conduit entrance through removable gland plate recommended.
- Use watertight conduit and connector only.
- Protect equipment against drilling chips.
- Door swing equal to door width.



**TORNATECH**

© Tornatech, Inc. Not for construction.  
Subject to change without notice.

BY DD/MM/YY

DRAWN BY ACD 28/02/23

FINAL APPROVAL FC 28/02/23



## LIMITED SERVICE PUMP CONTROLLER ACROSS THE LINE / 1 PHASE

**MODEL: GPL**

BUILT TO THE LATEST EDITION OF THE NFPA20 & NFPA70



DRAWING NUMBER  
**GPL-WS800/E**  
DWG REV. 0  
SHEET 1 OF 2



| Legend |                     |
|--------|---------------------|
| 1M     | Contactor           |
| AB     | Alarm Bell          |
| CB     | Circuit Breaker     |
| CR     | Control Relay       |
| CT     | Current Transformer |
| EB     | Electric I/O Board  |
| J      | Jumper              |
| LS     | Limit Switch        |
| PT     | Pressure Transducer |
| SA     | Surge Arrester      |
| ST     | Shunt Trip          |
| SV     | Solenoid Valve      |
| VMB    | Main Board          |
| XTR    | Transformer         |

**TORNATECH**© Tornatech, Inc. Not for construction.  
Subject to change without notice.


BY DD/MM/YY

DRAWN BY ACD 28/02/23

FINAL APPROVAL FC 28/02/23

**LIMITED SERVICE PUMP CONTROLLER  
ACROSS THE LINE / 1 PHASE****MODEL: GPL**

BUILT TO THE LATEST EDITION OF THE NFPA20 &amp; NFPA70

DRAWING NUMBER  
**GPL-WS800/E**  
DWG REV. 0  
SHEET 2 OF 2

\* Remove jumper to use this feature

\*\* Contact closes when emergency start is in "ON" position



**TORNATECH**

© Tornatech, Inc. Not for construction.  
Subject to change without notice.

BY DD/MM/YY

DRAWN BY ACD 28/02/23

FINAL APPROVAL FC 28/02/23

## LIMITED SERVICE PUMP CONTROLLER


**MODEL: GPL**

BUILT TO THE LATEST EDITION OF THE NFPA20 & NFPA70



DRAWING NUMBER  
**GPL-TD800/E**  
DWG REV. 0  
SHEET 1 OF 1

### Power Terminals Model : GPL 1 Phase



#### Notes:

- 1 - For proper wire sizing, refer to NFPA70 and NEC (USA) or CEC (Canada) or local code.
- 2 - Controller suitable for service entrance in USA.
- 3 - For more accurate motor connections refer to motor manufacturer or motor nameplate.
- 4 - Controller is phase sensitive. Incoming lines must be connected in ABC sequence.
- 5 - Field wiring and lug sizes are based on copper conductors only.  
Do not use aluminum conductors.

#### Circuit breaker (CB) Field Wiring according to Bending Space (AWG or MCM). TERMINALS L1 - L2

| Bending Space | 3 " (76 mm)  |              |             |             |             |             |
|---------------|--------------|--------------|-------------|-------------|-------------|-------------|
| HP            | 1            | 3            | 5           | 7.5         | 10          | 15          |
| Voltage       |              |              |             |             |             |             |
| 120           | 1x (10 to 1) | 1x (8 to 1)  | 1x (6 to 1) | 1x (4 to 1) | N/A         | N/A         |
| 208           | N/A          | 1x (10 to 1) | 1x (8 to 1) | 1x (6 to 1) | 1x (4 to 1) | 1x (3 to 1) |
| 220 to 240    | N/A          | 1x (10 to 1) | 1x (8 to 1) | 1x (8 to 1) | 1x (6 to 1) | 1x (3 to 1) |

(Use Copper Conductors Only)

#### Wiring Size for motor connection for Model GPL (AWG or MCM). TERMINALS T1 - T2

| HP         | 1            | 3            | 5           | 7.5         | 10          | 15          |
|------------|--------------|--------------|-------------|-------------|-------------|-------------|
| Voltage    |              |              |             |             |             |             |
| 120        | 1x (10 to 1) | 1x (8 to 1)  | 1x (6 to 1) | 1x (4 to 1) | N/A         | N/A         |
| 208        | N/A          | 1x (10 to 1) | 1x (8 to 1) | 1x (6 to 1) | 1x (4 to 1) | 1x (3 to 1) |
| 220 to 240 | N/A          | 1x (10 to 1) | 1x (8 to 1) | 1x (8 to 1) | 1x (6 to 1) | 1x (3 to 1) |

(Use Copper Conductors Only)

Drawing for information only.  
Manufacturer reserves the right to modify this drawing without notice.  
Contact manufacturer for "As Built" drawing.



**TORNATECH**

© Tornatech, Inc. Not for construction.  
Subject to change without notice.

BY DD/MM/YY

DRAWN BY ACD 28/02/23

FINAL APPROVAL FC 28/02/23

## LIMITED SERVICE PUMP CONTROLLER

**MODEL:GPL**

BUILT TO THE LATEST EDITION OF THE NFPA20 & NFPA70




DRAWING NUMBER  
**GPX-TD802/E**  
DWG REV. 0  
SHEET 1 OF 1

### Field Connections

Terminals Wire Size:  
24 - 12 AWG  
0.5 Nm

Remote Manual  
Lockout  
Remote Auto  
Deluge Valve  
Low Water Level



J25

Controller Terminal Strip

### Network Connections

Terminals Wire Size:  
Shielded Female Connector RJ45

Modbus TCP/IP RJ45

Located on Main Board



### Alarm Contacts

Terminals Wire Size:  
24 - 12 AWG  
0.5 Nm

Motor Run


Power Available

Normal Power  
Phase Reversal

Pump Room Alarm\*\*

Motor Trouble\*\*

(Field  
Programmable)



\* Remove jumper to use this feature  
\*\* Re-assignable




# Jockey Pump

(Optional Equipment)

## Talco ULV Jockey Pump

- High Quality Rotary Vane Pump
  - 1.8GPM @ 240PSI
- 1/3HP\* 200V-240V Electric Motor
  - Resilient Mounted
  - Permanently Lubricated
- Integrated Recirculation Relief Valve
  - Factory Set to 170PSI
  - No External Discharge
- Removable Mesh Suction Strainer
  - Cleanable & Reusable



Dimensions are approximate.

\*Motor HP subject to change without notice based on availability.

503-688-1231 [www.talcofire.com](http://www.talcofire.com) 6040 NE 112<sup>th</sup> Ave, Portland OR

**TALCO**  
— FIRE SYSTEMS —

# Commercial Pressure Switches

## Electromechanical Square D Brand 9013

### For power circuits, FRG, FHG, and G

#### Environmental characteristics

| Pressure switch type      |          | FRG                                                                                                                                                                                                             | FHG | G                           |
|---------------------------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-----------------------------|
| Conformity to standards   |          | UL 508, NEC Article 430-84, ANSI /NSF Standard 61, FDA 21 CFR.2600                                                                                                                                              |     |                             |
| Product Certifications    |          | UL File E12158 CCN NKPZ , CSA File LR 25490 Class 321106                                                                                                                                                        |     |                             |
| Protective treatment      |          | N/A                                                                                                                                                                                                             |     |                             |
| Ambient air temperature   | °C       | For operation, 0 °C (32 °F) min to 125 °C (257 °F) max<br>For storage, -30 °C (-22 °F) min to 70 °C (158 °F) max                                                                                                |     |                             |
| Fluids controlled         |          | Fresh water, or sea water (with Form Q)                                                                                                                                                                         |     |                             |
| Materials                 |          | Cover: polypropylene, Noryl® thermoplastic resin or equivalent for Type 3R, Component material in contact with fluid: flange, zinc plated or equivalent (fluid entry), nitrile or equivalent rubber (diaphragm) |     |                             |
| Operating position        |          | NEMA Type 1, and Type IP20 in any position, NEMA Type 3R in the vertical position only                                                                                                                          |     |                             |
| Vibration resistance      |          | —                                                                                                                                                                                                               |     |                             |
| Shock resistance          |          | —                                                                                                                                                                                                               |     |                             |
| Electric shock protection |          | —                                                                                                                                                                                                               |     |                             |
| Degree of protection      |          | NEMA Type 1, IP20 and NEMA Type 3R (some references) must be mounted in vertical position to maintain enclosure rating                                                                                          |     |                             |
| Operating rate            | cycles/m | 10                                                                                                                                                                                                              |     |                             |
| Repeat accuracy           |          | +/- 3 % of the range                                                                                                                                                                                            |     |                             |
| Fluid connection          |          | 1/8" NPSF internal, 1/4" NPSF internal, 1/2"NPT External, 1/4" Bayonet (barbed), 90 deg. Elbow 1/4" Bayonet, Four Way Flange, 3/8" NPSF (Internal), 1/4" Flare, other specials                                  |     |                             |
| Electrical connection     |          | 2 open side entries, 3/4" diameter, with two flats                                                                                                                                                              |     | 3 Conduit<br>1/2" Knockouts |

#### Contact block characteristics

|                             |        |                                                                                 |
|-----------------------------|--------|---------------------------------------------------------------------------------|
| Type of contacts            |        | One 2 pole, 2 N/C (4 terminal) contacts, snap action                            |
| Resistance across terminals | m Ω    | < 25                                                                            |
| Terminal referencing        |        | N/A                                                                             |
| Short-circuit protection    | A      | 5,000                                                                           |
| Connection                  |        | Screw clamp terminals. Clamping capacity up to #10 AWG (5.261 mm <sup>2</sup> ) |
| Electrical durability       | cycles | 100,000                                                                         |
| Mechanical durability       | cycles | 300,000                                                                         |

#### Electrical Ratings

| 1 Pole                             |             | FRG               |                   |                     | FHG ▲ ■            |                   |                     | G                 |                  |                     |
|------------------------------------|-------------|-------------------|-------------------|---------------------|--------------------|-------------------|---------------------|-------------------|------------------|---------------------|
| Power ratings of controlled motors | Voltage     | ~<br>1-phase      | ~<br>3-phase      | —                   | ~<br>1-phase       | ~<br>3-phase      | —                   | ~<br>1-phase      | ~<br>3-phase     | —                   |
|                                    | 32 V        | —                 | —                 | —                   | —                  | —                 | —                   | —                 | —                | —                   |
|                                    | 115 V       | 0.75 kW<br>(1 HP) | —                 | 0.18 kW<br>(.25 HP) | 1.1 kW<br>(1.5 HP) | 1.5 kW<br>(2 HP)  | 0.18 kW<br>(.25 HP) | 0.75 kW<br>(1 HP) | —                | 0.37 kW<br>(.50 HP) |
|                                    | 230 V       | 0.75 kW<br>(1 HP) | —                 | 0.18 kW<br>(.25 HP) | 1.5 kW<br>(2 HP)   | 2.2 kW<br>(3 HP)  | 0.18 kW<br>(.25 HP) | 1.5 kW<br>(2 HP)  | —                | 0.37 kW<br>(.50 HP) |
|                                    | 460 / 575 V | —                 | —                 | —                   | —                  | 0.75 kW<br>(1 HP) | —                   | 1.5 kW<br>(2 HP)  | —                | —                   |
| 2 Pole                             |             | ~<br>1-phase      | ~<br>3-phase      | —                   | ~<br>1-phase       | ~<br>3-phase      | —                   | ~<br>1-phase      | ~<br>3-phase     | —                   |
| Power ratings of controlled motors | Voltage     | ~<br>1-phase      | ~<br>3-phase      | —                   | ~<br>1-phase       | ~<br>3-phase      | —                   | ~<br>1-phase      | ~<br>3-phase     | —                   |
|                                    | 32 V        | —                 | —                 | 0.18 kW<br>(.25 HP) | —                  | —                 | —                   | —                 | —                | —                   |
|                                    | 115 V       | 0.75 kW<br>(1 HP) | 0.75 kW<br>(1 HP) | 0.18 kW<br>(.25 HP) | 1.5 kW<br>(2 HP)   | 2.2 kW<br>(3 HP)  | 0.37 kW<br>(.50 HP) | 1.5 kW<br>(2 HP)  | 2.2 kW<br>(3 HP) | 0.75 kW<br>(1 HP)   |
|                                    | 230 V       | 0.75 kW<br>(1 HP) | 0.75 kW<br>(1 HP) | 0.18 kW<br>(.25 HP) | 2.2 kW<br>(3 HP)   | 3.7 kW<br>(5 HP)  | 0.37 kW<br>(.50 HP) | 2.2 kW<br>(3 HP)  | 3.7 kW<br>(5 HP) | 0.75 kW<br>(1 HP)   |
|                                    | 460 / 575 V | —                 | —                 | —                   | —                  | 0.75 kW<br>(1 HP) | —                   | 3.7 kW<br>(5 HP)  | 3.7 kW<br>(5 HP) | —                   |

Note:  
Type FRG and G are all Form H


▲ Includes  
FHG 2, 3, 4, 9, 12, 13, 14, 19, 42, 44, 49

■ Includes  
FHG 22, 24, 29, 32, 33, 34, 39, 52, 54, 59

# Commercial Pressure Switches

Electromechanical Square D Brand 9013  
For power circuits G  
2-pole 2 N/C contacts  
Degree of protection IP20, NEMA Type 1, 7 & 9

## Flange Style



**Adjustable range of switching point**  
Contacts open on rising pressure  
**2 Pole**

| Fluid connections | 1/8" NPSF internal | 1/4" NPSF internal | 3/8" NPSF internal | 1/8" NPSF internal | 1/4" NPSF internal | 3/8" NPSF internal |
|-------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|
|-------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|

## References

|                                                                              |                             |                             |                             |                  |                  |                  |
|------------------------------------------------------------------------------|-----------------------------|-----------------------------|-----------------------------|------------------|------------------|------------------|
| <b>NEMA Type 1, IP20</b>                                                     | 9013GHG1                    | 9013GHG2                    | 9013GHG3                    |                  |                  |                  |
| <b>NEMA Type 7, NEMA Type 9</b>                                              |                             |                             |                             | 9013GHR1         | 9013GHR2         | 9013GHR3         |
| <b>Fluids / Pressure controlled</b>                                          | Water or Air                | Water or Air                | Water or Air                | Water or Air     | Water or Air     | Water or Air     |
| <b>Pressure range</b>                                                        |                             |                             |                             |                  |                  |                  |
| <b>Cut-Out PSIG (bar)</b>                                                    | 60-200                      | 60-200                      | 60-200                      | 65-200           | 65-200           | 65-200           |
| <b>Cut-In PSIG (bar)</b>                                                     | 40-170                      | 40-170                      | 40-170                      | 35-150           | 35-150           | 35-150           |
| <b>Weight lbs (kg)</b>                                                       | 2 lbs (0.91)                | 2 lbs (0.91)                | 2 lbs (0.91)                | 8 lbs (3.62)     | 8 lbs (3.62)     | 8 lbs (3.62)     |
| <b>Complementary characteristics not shown under general characteristics</b> |                             |                             |                             |                  |                  |                  |
| <b>Differential PSIG (bar)</b>                                               | 20-40 (1.4-2.8)             | 20-40 (1.4-2.8)             | 20-40 (1.4-2.8)             | 30-50 (2.1-3.5)  | 30-50 (2.1-3.5)  | 30-50 (2.1-3.5)  |
| <b>Maximum permissible pressure PSIG (bar)</b>                               | 80 (5.5)                    | 80 (5.5)                    | 80 (5.5)                    | 80 (5.5)         | 80 (5.5)         | 200 (13.8)       |
| <b>Mechanical life</b>                                                       | 300, 000 operating cycles   |                             |                             |                  |                  |                  |
| <b>Cable entry</b>                                                           | 3 Conduit<br>1/2" Knockouts | 3 Conduit<br>1/2" Knockouts | 3 Conduit<br>1/2" Knockouts | 2<br>3/4"-14 NPT | 2<br>3/4"-14 NPT | 2<br>3/4"-14 NPT |
| <b>Pressure switch type</b>                                                  | Diaphragm                   |                             |                             |                  |                  |                  |

## Ordering Information

## Pressure Codes

Below is the pressure code table.  
Existence of a code does not imply that the code is available for any or all devices.

| Settings                  | Code |
|---------------------------|------|
| 20-40 PSI                 | J20  |
| 30-50 PSI                 | J21  |
| 40-20 PSI                 | J23  |
| 40-60 PSI                 | J24  |
| 60-80 PSI                 | J25  |
| 70-90 PSI                 | J26  |
| 70-100 PSI                | J28  |
| 75-100 PSI                | J29  |
| 80-100 PSI                | J30  |
| 90-120 PSI                | J31  |
| 100-80 PSI                | J51  |
| 100-125 PSI               | J53  |
| 110-125 PSI               | J54  |
| 110-150 PSI               | J56  |
| 120-150 PSI               | J57  |
| 125-150 PSI               | J58  |
| 125-175 PSI               | J60  |
| 130-175 PSI               | J61  |
| 140-170 PSI               | J66  |
| 140-175 PSI               | J62  |
| 145-175 PSI               | J63  |
| 150-120 PSI               | J64  |
| 150-175 PSI               | J67  |
| 215-250 PSI               | J65  |
| Specify pressure settings | J99  |

- 1 Specify Class 9013 Type G.
- 2 Select pressure code and add code designation to end of type number. Be sure that pressure code falls within the limits of the device as shown in the device listings.
- 3 If special features are desired, add the appropriate Form letter to the Class and Type. Arrange Form letters in alphabetical sequence when ordering more than one special feature.
- 4 Place packaging code at end of sequence with other forms when ordering. If no packaging code is indicated, devices will be shipped individually packaged.  
For standard pack of 10 devices per box C10  
Available on GHG, GHG, GSB, and GSG

See page 25 for Form C10.

**TALCO** FIRE  
SYSTEMS



RESIDENTIAL & COMMERCIAL FIRE PUMP SPECIALISTS

6040 NE 112TH AVE. PORTLAND, OREGON 97220

PHONE: 800-878-8055 [WWW.TALCOFIRE.COM](http://WWW.TALCOFIRE.COM)

# Valves & Fittings



Model L399 OS&Y Gate Valve

cULus Listed, FM Approved

Product Description

The Reliable Model L399 OS&Y Gate valves are UL Listed and FM Approved resilient seated indicating control valves for fire protection systems. Reliable L399 OS&Y Gate Valves are available with grooved outlets that conform to AWWA C606 / ISO 6182-12, ANSI/ASME B16.1 flanged outlets compatible with both Class 150 and Class 125 flanges, and ISO 7005-1 flanged outlets compatible with both PN10 and PN16 flanges. They are available in 2" (50mm), 2-1/2" (65mm), 3" (80mm), 4" (100mm), 6" (150mm), 8" (200mm), 10" (250mm), and 12" (300mm) nominal sizes. The valves are listed for 300 psi (20.7 bar) working pressure. Verify that appropriate end connections and fittings are used for the system pressure prior to installation.

Maintenance

The owner is responsible for maintaining the fire protection system in proper operating condition. Any system maintenance or testing that involves placing a control valve out of service will eliminate the fire protection that is provided by the fire protection system.

The Reliable OS&Y Gate valves and associated equipment shall periodically be given a thorough inspection and test. NFPA 25, "Inspection, Testing and Maintenance of Water Based Fire Protection Systems," provides minimum maintenance requirements.

Ordering Information

Specify the following when ordering:

Reliable Model L399 OS&Y Gate Valve

Valve Size

End Connection

- Flange x Flange
- Flange x Groove
- Groove x Groove



Flange x Flange



Flange x Groove



Groove x Groove

Guarantee

For Reliable Automatic Sprinkler Co., Inc. guarantee, terms, and conditions, visit [www.reliablesprinkler.com](http://www.reliablesprinkler.com).

End Configuration Options

Table A

| Model          | End Connections | Sizes in (mm)                                                                     | Approvals                 |
|----------------|-----------------|-----------------------------------------------------------------------------------|---------------------------|
| REL-OSY-L399F  | Flange x Flange | 2" (50), 2-1/2" (65), 3" (80), 4" (100), 6" (150), 8" (200), 10" (250), 12" (300) | cULus Listed, FM Approved |
| REL-OSY-L399FG | Flange x Groove |                                                                                   |                           |
| REL-OSY-L399GG | Groove x Groove |                                                                                   |                           |

## OS&Y Gate Valves

### Technical Specifications

**Pressure Rating:**  
300 psi (20.7 bar)

### Material Specifications

**Body:** Ductile Iron A536 65-45-12  
**Wedge:** Ductile Iron EPDM Coated  
**Wedge Nut:** Stainless Steel AISI 304  
**Stem:** Stainless Steel AISI 304  
**Bonnet:** Ductile Iron A536 65-45-12  
**Gasket:** EPDM Commercial  
**Packing:** Graphite  
**Stem Nut:** Bronze ASTM B62  
**Handwheel:** Ductile Iron A536 65-45-12

### End Connections

Groove x Groove  
 Flange x Groove  
 Flange x Flange

### Specifications

Groove: AWWA C606 / ISO 6182-12  
 ANSI/ASME Flanges: ANSI/ASME B16.1  
 Class 125 / 150 with raised face  
 ISO Flanges: ISO 7005-1 PN10 / PN16 with raised face

### Listings and Approvals


cULus Listed  
 FM Approved



## Reliable OS&Y Gate Valve Dimensions

Figure 1

**Note:** Flanged valve shown.  
 Dimension C (end to end) is the same for all end configurations.



## Reliable OS&Y Gate Valve Dimensions - in. (mm)

Table B

| Valve Size  | A              | B                | C             | Tap Size | Approximate Number of Handwheel Turns from Open to Close |
|-------------|----------------|------------------|---------------|----------|----------------------------------------------------------|
| 2" (50)     | 7-3/16" (183)  | 16-3/16" (411)   | 7" (178)      | 1/2" NPT | 12                                                       |
| 2-1/2" (65) | 7-3/16" (183)  | 16-3/16" (411)   | 7-1/2" (191)  | 1/2" NPT | 16                                                       |
| 3" (80)     | 9-15/16" (253) | 18-3/16" (462)   | 8" (203)      | 1/2" NPT | 16                                                       |
| 4" (100)    | 9-15/16" (253) | 20-1/4" (514)    | 9" (229)      | 1/2" NPT | 20                                                       |
| 6" (150)    | 12-1/16" (306) | 27-15/16" (709)  | 10-1/2" (267) | 3/4" NPT | 30                                                       |
| 8" (200)    | 14" (355)      | 36-1/3" (922)    | 11-1/2" (292) | 3/4" NPT | 33                                                       |
| 10" (250)   | 17-1/2" (445)  | 43-15/16" (1116) | 13" (330)     | 1" NPT   | 41                                                       |
| 12" (300)   | 17-1/2" (445)  | 51-3/16" (1300)  | 14" (356)     | 1" NPT   | 50                                                       |

**Note:** Model L399 OS&Y valves manufactured before August 2022 may have a 1/4" FNPT tap on all sizes of valves.


Reliable OS&Y Gate Valve Weights

Table C

| Valve Size<br>in (mm) | FLG x FLG<br>lbs (kg) | FLG x GRV<br>lbs (kg) | GRV x GRV<br>lbs (kg) |
|-----------------------|-----------------------|-----------------------|-----------------------|
| 2" (50)               | 33.9 (15.4)           | 33.8 (15.4)           | 25.9 (11.8)           |
| 2-1/2" (65)           | 39.8 (18.1)           | 35.5 (16.1)           | 29.7 (13.5)           |
| 3" (80)               | 46 (20.9)             | 41.2 (18.7)           | 34.8 (15.8)           |
| 4" (100)              | 58.4 (26.6)           | 48.7 (22.1)           | 38 (17.3)             |
| 6" (150)              | 99.9 (45.4)           | 86.4 (39.3)           | 71.9 (32.7)           |
| 8" (200)              | 183.2 (83.3)          | 171.2 (77.8)          | 147.6 (67.1)          |
| 10" (250)             | 230.2 (104.7)         | 211.6 (96.2)          | 181.7 (82.6)          |
| 12" (300)             | 386.8 (175.8)         | 359.7 (163.5)         | 308.4 (140.2)         |

Friction Loss

Figure 2



Supervisory Switch Compatibility

Reliable Model L399 OS&Y gate valves are compatible with multiple supervisory switches manufactured by others. These switches are designed to monitor the valve in a normally open condition and utilize a preexisting groove machined in the valve stem during manufacture. Reliable Model L399 OS&Y gate valve are provided with this groove and should not require any modification to the valve stem in order to install the supervisory switch. All sizes of Reliable Model L399 OS&Y gate valve are compatible with the following supervisory switches:

- Potter® OSYSU Series Supervisory Switch
- Potter® OSYSU-CRH Series Supervisory Switch
- Potter® OSYSU-EX Series Supervisory Switch
- Potter® OSYSU-EX-O Series Supervisory Switch
- Safe Signal® OSY2 Series Supervisory Switch
- Safe Signal® OSY2A Series Supervisory Switch
- Safe Signal® OSYEXP Series Supervisory Switch

## Features

- NEMA 4X\* (IP 65) and 6P (IP 67)
- *\*Enclosure is 4X. For additional corrosion protection of mounting hardware, use model OSYSU-2 CRH*
- -40° to 140° (-40°C to 60°C) operating temperature range
- Visual switch indicators
- Two conduit entrances
- Adjustable length trip rod
- Accommodates up to 12AWG wire
- Three position switch detects tampering and valve closure
- Knurled mounting bracket prevents slipping
- Fine adjustment feature for fast, easy installation
- RoHS compliant
- One or two SPDT contact models (-1,-2)

## NOTICE

Before any work is done on the fire sprinkler or fire alarm system, the building owner or their authorized representative shall be notified. Before opening any closed valve, ensure that opening the valve will not cause any damage from water flow due to open or missing sprinklers, piping, etc.



**Important:** This document contains important information on the installation and operation of OS&Y valve supervisory switches. Please read all instructions carefully before beginning installation. A copy of this document is required by NFPA 72 to be maintained on site.

## Description

The OSYSU is used to monitor the open position of an OS&Y (outside screw and yoke) type gate valve. This device is available in two models; the OSYSU-1, containing one set of SPDT (Form C) contacts and the OSYSU-2, containing two sets of SPDT (Form C) contacts. These switches mount conveniently to most OS&Y valves ranging in size from 2" to 12" (50mm to 300mm). They will mount on some valves as small as ½" (12,5mm).

The cover is held in place by two tamper resistant screws that require a special tool to remove. The tool is furnished with each device.

## Testing

The operation of the OSYSU and its associated protective monitoring system shall be inspected, tested, and maintained in accordance with all applicable local and national codes and standards and/or the Authority Having Jurisdiction (manufacturer recommends quarterly or more frequently). A minimum test shall consist of turning the valve wheel towards the closed position. The OSYSU shall operate within the first two revolutions of the wheel. Fully close the valve and ensure that the OSYSU does not restore. Fully open the valve and ensure that the OSYSU restores to normal only when the valve is fully opened.

## CAUTION

Close the valve fully to determine that the stem threads do not activate the switch. The switch being activated by the stem threads could result in a **false valve open** indication.

## Technical Specifications

|                           |                                                                                                                                                                                                              |
|---------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Dimensions                | See Fig 8                                                                                                                                                                                                    |
| Weight                    | 1.6 lbs (0,73 kg)                                                                                                                                                                                            |
| Enclosure                 | Cover: Die Cast Finish: Red Powder Coat<br>Base: Die Cast Finish: Black Powder Coat<br>All parts have corrosion resistant finishes                                                                           |
| Cover Tamper              | Tamper Resistant Screws<br>Optional Cover Tamper Switch Available                                                                                                                                            |
| Contact Ratings           | OSYSU-1: One Set of SPDT (Form C)<br>OSYSU-2: Two Sets of SPDT (Form C)<br>10.0 Amps at 125/250 VAC<br>2.0 Amps at 30VDC Resistive<br>10 mAmps minimum at 24 VDC                                             |
| Environmental Limitations | -40° F to 140°F (-40°C to 60°C)<br>NEMA 4X (IP 65) and NEMA 6P (IP 67) Enclosure (Use suitably rated conduit and connector)<br>Indoor or Outdoor Use (See OSYSU-EX Bulletin 5400705 for Hazardous locations) |
| Conduit Entrances         | Two Knockouts for 1/2" conduit provided (See Notice on Page 6 and Fig. 9 on Page 5)                                                                                                                          |
| Service Use               | NFPA 13, 13D, 13R, 72                                                                                                                                                                                        |

Specifications subject to change without notice

# Reliable®

## Model BFG-300 Supervised Butterfly Valve Grooved

cULus Listed, FM Approved

### Product Description

The Reliable Model BFG-300 Supervised Butterfly valves are cULus Listed and FM Approved for fire protection systems. Reliable Supervised Butterfly Valves have AWWA C606 grooved end connections. They are available in 2-1/2" (65mm), 3" (80mm), 4" (100mm), 6" (150mm), and 8" (200mm) nominal sizes. The valves are listed for 300 psi (20.7 bar) working pressure. The maximum working temperature for the valves is 250°F (120°C).

### Maintenance

The owner is responsible for maintaining the fire protection system in proper operating condition. Any system maintenance or testing that involves placing a control valve out of service will eliminate the fire protection that is provided by the fire protection system.

The Reliable Supervised Closed Butterfly valves and associated equipment shall periodically be given a thorough inspection and test. NFPA 25, "Inspection, Testing and Maintenance of Water Based Fire Protection Systems," provides minimum maintenance requirements.

### Guarantee

For Reliable Automatic Sprinkler Co., Inc. guarantee, terms, and conditions, visit [www.reliablesprinkler.com](http://www.reliablesprinkler.com).



Supervised Grooved Butterfly  
Valve - Supervised Open



Supervised Grooved Butterfly  
Valve - Supervised Closed

### Ordering Information

Specify the following when ordering:

#### Model BFG-300 Butterfly Valve Supervision

- Valve Supervised Open (yellow indicator)
- Valve Supervised Closed (white indicator)


#### Valve Size

- 2-1/2" (65mm)
- 3" (80mm)
- 4" (100mm)
- 6" (150mm)
- 8" (200mm)


### Reliable Supervised Butterfly Valve Wiring Diagram - Valve in Supervised Position

Figure 1

Supervised Normally Open Valve



Supervised Normally Closed Valve




**Notes:** Rated: 5A-1/6HP-125/250VAC  
0.5A - 125VDC  
0.25A - 250VDC

# Check Valves

UL LISTED AND FM APPROVED

WWW.FPPI.COM



3198 LIONSHEAD AVE  
CARLSBAD, CA 92010  
+ 1 (760) 599-1168  
+ 1 (800) 344-1822  
+ 1 (800) 344-3775 FAX

LISTED VALVE NOW  
AVAILABLE IN  
1½" SIZE



- Brass Body\* (C38000) for superior corrosion resistance
- Listed valves available in the following sizes: 1 ½"\*\*, 2", 2 ½", 3" and 4"
- Available Grooved, Threaded, or Thread by Groove reducing the need for additional fittings and minimizing installation time.
- Pressure rated to up to 300 PSI
- Tapped and plugged for easy use of accessories such as ball drips or gauges




\*Contains lead. Not for use in water systems intended for human consumption.

\*\*1 ½" size is UL/ULC listed only

**INSIST** ON  
FPPI®

# NFPA20 Sensing Line Detail



Pressure Sensing Lines constructed in accordance with NFPA 20:  
All brass or copper components, orifice unions at connections to  
both discharge piping & controller valve assembly, minimum 60"  
hard copper tubing between unions.